

AD-A156 185 NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
GOVE DIKE (NH 00135) (U) CORPS OF ENGINEERS WALTHAM MA  
NEW ENGLAND DIV JUL 78

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
GOVE DIKE (NH 00135). (U) CORPS OF ENGINEERS WALTHAM MA  
NEW ENGLAND DIV JUL 78

1/1

UNCLASSIFIED F/G 13/13 NL


F/G 13/13

NL

END

FILMED

OTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A


AD-A156 185

PISCATAQUA RIVER BASIN  
NOTTINGHAM, NEW HAMPSHIRE

GOVE DIKE  
NH 00135

STATE NO 184.03


PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



DTIC FILE COPY

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

JULY 1978



85 06 12 056

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00135	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Gove Dike  NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1978
		13. NUMBER OF PAGES 37
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY,  Piscataqua River Basin Nottingham, New Hampshire Tributary of Pawtucketway River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  The dike is about 9 ft. high and 270 ft. long. It is an earthen embankment contained between a nearly vertical wall of rounded boulders upstream and a vertical dry masonry wall downstream. The dike is in fair condition. The owner should monitor seepage weekly as well as clear brush on the access road and downstream of the dike.		

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT

Identification No.: NH00135  
Name of Dam: Gove Dike  
Town: Nottingham  
County and State: Rockingham County, New Hampshire  
Stream: Tributary of Pawtuckaway River  
Date of Inspection: 30 May 1978

BRIEF ASSESSMENT

Gove Dike is about 9 feet high, 20 feet wide at the crest, and 270 feet long (as measured in the field). It is a 136-year old earthen embankment contained between a nearly vertical wall of rounded boulders upstream and a vertical dry masonry (stone) wall downstream. An unpaved road occupies the crest of the dike. This dike and Dolloff and Drown's Dams form the impoundment system of Pawtuckaway Pond. The pond is used now for recreational purposes. It is 3 miles long, has a surface of about 900 acres, and maximum storage is 11,700 acre-feet.

The dike is in fair condition. Major concerns with regard to its long-term integrity are: the overtopping potential caused by the inadequate spillway discharge capacity at Dolloff and Drown's Dams, seepage at the downstream toe (less than 0.01 cfs), and a 6-inch bulge in the downstream vertical dry masonry wall.

The dike has no outlets. The test flood would overtop the dike at its lowest point by 2.9 feet.

The owner, New Hampshire Water Resources Board (NHWRB), should within two years implement the results, after evaluation of the following: assess further all factors relating to overtopping and to the inadequacy of the spillways of the system and design remedial measures for the seepages at the downstream toe of the dike and the bulge in the downstream vertical dry masonry wall. Within one year, NHWRB should implement the following operation and maintenance measures: monitor seepage weekly, clear brush on the access road and downstream of the dike, and establish a surveillance and warning program to be exercised during floods.

*Warren A. Guinan*  
Warren A. Guinan  
Project Manager  
N.H. P.E. No. 2339

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers (OCE), Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	



## CONTENTS

Title	Page
BRIEF ASSESSMENT	
REVIEW BOARD PAGE	
PREFACE.....	i
CONTENTS.....	ii
OVERVIEW PHOTO.....	iii
LOCATION MAP.....	iv

## REPORT

### Section

1	PROJECT INFORMATION.....	1
1.1	General.....	1
1.2	Description of Project.....	1
1.3	Pertinent Data.....	3
2	ENGINEERING DATA.....	6
2.1	Design.....	6
2.2	Construction.....	6
2.3	Operation.....	6
2.4	Evaluation.....	6
3	VISUAL INSPECTION.....	7
3.1	Findings.....	7
3.2	Evaluation.....	8
4	OPERATIONAL PROCEDURES.....	9
4.1	Procedures .....	9
4.2	Maintenance of Dike .....	9
4.3	Maintenance of Operating Facilities .....	9
4.4	Description of Any Warning System in Effect .....	9
4.5	Evaluation.....	9
5	HYDROLOGY AND HYDRAULIC ANALYSIS.....	10
5.1	Evaluation of Features.....	10
6	STRUCTURAL STABILITY.....	12
6.1	Evaluation of Structural Stability.....	12
7	ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES.....	13
7.1	Dike Assessment.....	13
7.2	Recommendations.....	14
7.3	Remedial Measures.....	14

## APPENDICES

### Designation

CHECK LIST - VISUAL INSPECTION.....	A
INSPECTION REPORTS/SKETCHES.....	B
PHOTOGRAPHS (Figures 2 - 6).....	C
HYDROLOGY/HYDRAULICS.....	D
INVENTORY DATA.....	E








Figure 1 - Overview of upstream face of Gove Dike.



Reprinted by permission of the Department of Resources and Economic Development, Concord, N.H. 03301, and the copyright owners, The National Survey, Chester, VT. 8-17-78

SCALE IN MILES



MAP BASED ON STATE OF NEW HAMPSHIRE-  
STATE OF MAINE OFFICIAL HIGHWAY MAPS

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV NEW ENGLAND	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
GOVE DIKE			
LOCATION MAP			
PAWTUCKAWAY POND		NEW HAMPSHIRE	
		SCALE 1" = 5 MI.	
		DATE: JULY 1978	

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT  
GOVE DIKE

SECTION I  
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols & Company, Inc. under a letter of May 3, 1978 from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0329 has been assigned by the Corps of Engineers for this work.

b. Purpose.

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Gove DiKE is located in the Town of Nottingham, New Hampshire. Gove DiKE, together with Dolloff and Drown's Dams, form the structural barrier system that impounds Pawtuckaway Pond. Gove DiKE dams an unnamed tributary of the Pawtuckaway River approximately 0.7 mile upstream of their confluence. The Pawtuckaway then flows for about 2.5 miles to its confluence with the Lamprey River, a major tributary in the Piscataqua River Basin. The dike is shown on U.S.G.S. Quadrangle, Mt. Pawtuckaway, New Hampshire, with coordinates approximately at N 43° 04' 54", W 71° 07' 59", Rockingham County, New Hampshire (see location map page iv).

b. Description of Dike and Appurtenances. Gove Dike is a low earthen embankment with the upstream side partially faced with a nearly vertical wall of rounded boulders. The downstream face consists of a dry masonry wall. The dike, as measured in the field, is about 20 feet wide at the crest, 270 feet in length, and 9 feet in height above the downstream toe. However, past inspection reports and other records (see Appendix B) reflect that the dike is 350 feet in length, while the maximum structural height is 11 feet as given in the Corps of Engineers' Inventory of March 1974. An unpaved roadway runs along the crest of the dike (see sketches in Appendix B). It is evident that fill has been placed sometime prior to 1978 to accommodate another road near the right (westerly) end of the dike.

c. Size Classification. Intermediate (Hydraulic height - 8 feet, Storage - 11,700 acre-feet) based on storage ( $\geq 1000$  to  $< 50,000$  acre-feet) as given in OCE Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Significant hazard. A major breach in the dike would probably result in the loss of less than 10 lives and appreciable property damage.

e. Ownership. The present dike, along with Dolloff and Drown's Dams, are reported to have been built sometime between the years 1839 and 1842 by the Newmarket Manufacturing Company for the purpose of impounding Pawtuckaway Pond for use in their milling operations. Ownership passed on to the Lamprey River Improvement Company, a subsidiary of New Hampshire Gas and Electric Company, sometime prior to 1917. The New Hampshire Water Resources Board (NHWRB) purchased the three structures for one dollar in 1955 from the New Hampshire Gas and Electric Company.

f. Operator. Mr. Vernon K. Knowlton, Chief Engineer, New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301 is responsible for the operation of the dams on Pawtuckaway Pond. Phone (603) 271-3406.

g. Purpose of Dike. The dike and dams impounding Pawtuckaway Pond were originally constructed to provide greater industrial storage for the Newmarket Manufacturing Company located in Newmarket, New Hampshire. Later, under the ownership of the Lamprey River Improvement Company, Pawtuckaway Pond was utilized primarily as upstream storage for generation of hydroelectricity for the region, with some recreational usage. Pawtuckaway Pond is presently being used for recreational purposes only.

h. Design and Construction History. Little information was found concerning the original design and construction of the dike. It is believed that the structure is basically an earth-fill dike faced with vertical dry masonry walls. A 1918 report recommended that an overflow area be created by lowering the crest 2.5 feet over a distance of 125 feet at the western end of the dike. A letter dated 1919 from the owner to the state regulatory agency indicates that this construction was started. Visual inspection found no evidence of an overflow area. Presently, the dike also serves as an unpaved year-round road.

i. Normal Operational Procedures. Not applicable; Gove Dike has no outlet facilities. No written maintenance procedures were found.

### 1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 20.66 square miles (13,225 acres) of predominantly wooded terrain.

#### b. Discharge at Damsite (Dike)

- (1) Outlet works (conduits) - none
- (2) Maximum known discharge at damsite (dike) is unknown.
- (3) Ungated spillway capacity at maximum pool elevation - not applicable.
- (4) Gated spillway capacity at pool elevation - not applicable.
- (5) Gated spillway capacity at maximum pool elevation - not applicable.
- (6) Total spillway capacity at maximum pool elevation - not applicable.

c. Elevation (ft. above MSL) based on elevation of 250 shown on U.S.G.S. Quadrangle sheet and assumed to be spillway elevation at Dolloff Dam, Pawtuckaway Pond. (See Dolloff Dam Inspection Report.)

- (1) Top of dike - 253.6
- (2) Maximum pool - design surcharge - unknown
- (3) Full flood control pool - not applicable

- (4) Recreation pool - 250
- (5) Spillway crest - not applicable
- (6) Upstream portal invert diversion tunnel - none
- (7) Streambed at centerline of dike - 244.4 (downstream toe measured at time of inspection)

(8) Maximum tailwater - unknown

d. Reservoir (miles)

- (1) Length of maximum pool - 3.0
- (2) Length of recreation pool - 3.0
- (3) Length of flood control pool - not applicable

e. Storage (acre-feet)

- (1) Recreation pool - 11,500
- (2) Flood control pool - not applicable
- (3) Design surcharge - unknown
- (4) Top of dike - 11,700 (storage based on Dolloff Dam)

f. Reservoir Surface (acres)

- (1) Top of dike - 1015
- (2) Maximum pool - 975 (based on Dolloff Dam)
- (3) Flood control pool - not applicable
- (4) Recreation pool - 903
- (5) Spillway crest - not applicable

g. Dike

(1) Type - earthen embankment with its upstream face partially covered with round boulders, and a dry masonry downstream face; both faces being nearly vertical.

- (2) Length - 270' (measured)  
- 350' (from past inspection records)

# PERIODIC INSPECTION CHECK LIST

PROJECT Gove Dike, New Hampshire

DATE May 31, 1978

PROJECT FEATURE Dike Embankment

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

## AREA EVALUATED

## CONDITION

Crest Elevation	253.6 ft. MSL
Current Pool Elevation	250.1 ft. MSL
Maximum Impoundment to Date	Unknown
Surface Cracks	None
Pavement Condition	Not paved
Movement or Settlement of Crest	None
Lateral Movement	Minor bulging of dry masonry wall on downstream side of dam
Vertical Alignment	Good
Horizontal Alignment	Good (See "Lateral Movement", above)
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	None
Trespassing on Slopes	Some bulldozing on downstream side of west abutment
Sloughing or Erosion of Slopes or Abutments	None
Rock Slope Protection - Riprap Failures	None
Unusual Movement or Cracking at or near Toes	None
Unusual Embankment or Downstream Seepage	Two small seepages near toe of dam, one close to west abutment and one near center of dam
Piping or Boils	None
Foundation Drainage Features	None known
Toe Drains	None known
Instrumentation System	None known

# VISUAL INSPECTION CHECKLIST

## PARTY ORGANIZATION

PROJECT Gove Dike, New Hampshire

DATE May 30, 1978

TIME 2:00 P.M.

WEATHER Sunny, hot

W.S. ELEV. 250 U.S. 244 DN.S.

### PARTY:

(ground surface below dike)

- |                             |           |
|-----------------------------|-----------|
| 1. <u>Warren Guinan</u>     | 6. _____  |
| 2. <u>Robert Langen</u>     | 7. _____  |
| 3. <u>Stephen Gilman</u>    | 8. _____  |
| 4. <u>Ronald Hirschfeld</u> | 9. _____  |
| 5. _____                    | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Hydraulics/Hydrology</u>	<u>R. Langen</u>	
2. <u>Structural Stability</u>	<u>S. Gilman</u>	
3. <u>Soils and Geology</u>	<u>R. Hirschfeld</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		



APPENDIX A  
CHECK LIST - VISUAL INSPECTION

(3) The NHWRB should develop a written operational procedure to follow in the event of flood flow conditions of imminent dike failure that could include round-the-clock surveillance and a warning system. The warning system should be included also in the written procedures of "Project Linkup", a disaster plan involving Civil Defense (as coordinator), state agencies, and town officials. "Project Linkup", at this time, is in draft form awaiting the Governor's approval.

7.3 b. below should be implemented by the owner within one year.

d. Need for Additional Investigation. The information available from the visual inspection indicates that the problems are overtopping and seepage. These problems require the attention of a competent engineer to design or specify remedial measures to rectify the problems. If left unattended, the problems could lead to instability of the structure.

## 7.2 Recommendations

a. Facilities. The New Hampshire Water Resources Board should accomplish the remedial measures resulting from the following:

(1) Evaluate further the potential for overtopping and the inadequacy of the spillways for the total impoundment system of Pawtuckaway Pond.

(2) Design or specify the remedial measures needed to eliminate or control the seepage along the downstream toe.

(3) Design the correctional measures for the bulge in the downstream dry-masonry wall.

(4) Remove small trees and brush.

(5) Consider measures required to shape the shoulders and pave the road to eliminate possible erosional problems.

## 7.3 Remedial Measures

a. Alternatives. The NHWRB should consider as alternatives, pending implementation and results of the above recommendations, (see also Dolloff Dam Report) the following:

(1) Purchase downstream land that would be adversely impacted by failure of Gove Dike and restrict human occupancy.

(2) Enhance the stability of Gove Dike to permit overtopping by the test flood without failure.

### b. Operation and Maintenance Procedures.

(1) The seepage at the downstream toe should be monitored on a weekly basis.

(2) The tree and brush growth on the dike and downstream for at least 20 feet should be removed and kept free in the future.

SECTION 7  
ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection indicates that Gove Dike is in fair condition. The major concerns affecting the overall long-term integrity of the dike are as follows:

- (1) The overtopping potential.
- (2) The seepage at the downstream toe.
- (3) The bulge in the downstream vertical dry masonry wall.
- (4) The brush and trees growing on either side of the unpaved roadway.
- (5) The possibility of erosion of the unpaved roadway caused by surface runoff from the approach and egress roadways at either end of the dike.
- (6) The possibility of erosion of the unpaved roadway if the dike is overtopped.

Because Gove Dike is an integral part of the Pawtuckaway Pond impoundment system that includes Drown's and Dolloff Dams, its relationship to the test flood required hydrologic and hydraulic analyses of all three structures. Under conditions of the test flood all structures are overtopped. The spillway capacity of the combined system is considered inadequate.

Assuming that Drown's and Dolloff Dams do not fail, Gove Dike would be overtopped by 2.9 feet under conditions of the test flood. This depth of overtopping takes into consideration the fact that Gove Dike is about one foot higher than the emergency spillway at Drown's Dam and the low ground adjacent to the left abutment at Dolloff Dam. Gove Dike, however, has stood the test of time - at least 136 years.

b. Adequacy of Information. The information available is such that the assessment of the safety of the dike must be based on the visual inspection.

c. Urgency. The recommendations enumerated in 7.2 below should be implemented by the owner, NHWRB, within two years. The operation and maintenance measures enumerated in

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. Visual observations indicated three potential structural problems: (1) seepage downstream of the toe of the dike, (2) localized bulging of the nearly vertical dry masonry wall which comprises the downstream face of the dike, and (3) trees and brush growing on the dike. (See Section 3.1 b.)

b. Design and Construction Data. No design and construction data are available except the sketch contained in a 1918 condition report that was copied from an 1889 document. Apparently the dike was built during the period between 1839 and 1842 and has remained intact for at least 136 years. (See Appendix B.)

c. Operating Records. No operating records pertaining to the structural stability were disclosed.

d. Post-Construction Changes. Some fill has apparently been placed against the downstream face at the right abutment up to approximately the level of the crest roadway. Also, numerous large boulders (4 to 5 feet in size) have apparently been dumped immediately downstream of the downstream dry masonry wall near both ends of the dike. Neither of these changes would have any adverse impact on the structural stability of the dike.

e. Seismic Stability. This dike is in Seismic Zone 2 and hence does not have to be evaluated for seismic stability according to the OCE Recommended Guidelines.

d. Overtopping Potential. Gove Dike in conjunction with Dolloff and Drown's Dams, is unable to store to test flood without overtopping. The water depth over the lowest point of the crest of the dike was calculated to be 2.9 feet.

SECTION 5  
HYDROLOGY AND HYDRAULIC ANALYSIS

5.1 Evaluation of Features

a. Design Data. No original hydrologic and hydraulic design data (1839-1842) were found for the structures impounding Pawtuckaway Pond. Hydrologic and hydraulic information, however, dating from the ownership by the Lamprey River Improvement Company of the dikes and dams to the present ownership by the New Hampshire Water Resources Board were found and assessed to determine their acceptability in evaluating the overtopping potential of Gove Dike.

Gove Dike is classified as being intermediate in size having a maximum storage of 11,700 acre-feet.

To determine the hazard classification for Gove Dike, the impact of failure of the dike at maximum pool was assessed using Guidance for Estimating Downstream Dam Failure Hydrographs issued by the Corps of Engineers. The analysis covered the reach extending from the dike to the village of West Epping, a distance of about 3 miles. Failure of Gove Dike at maximum pool would probably result in an increase in stage of 6.6 feet at West Epping. An increase in water depth of this magnitude would probably result in the loss of less than 10 lives, sever State Route 156, and damage some agricultural lands.

As a result of the analysis described above, Gove Dike was classified - Significant Hazard. Using OCE Recommended Guidelines for Safety Inspection of Dams, the recommended spillway test flood is the Probable Maximum Flood. The test flood discharge for Pawtuckaway Pond, having a drainage area of 20.66 square miles, was determined to be 11,200 cfs.

b. Experience Data. No information regarding past overtopping of the structure was found.

c. Visual Observations. No visual evidence was found of damage to the structure caused by overtopping at the time of the inspection. At least one house on the reservoir's east bank near the dike has its first floor at or below the crest of the dike.

SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedures

The NHWRB has operated Pawtuckaway Pond since 1955. Gove Dike has no outlet facilities. The level of the impoundment is controlled by discharge through Dolloff and Drown's Dams. The water level during the recreational season is maintained reasonably constant (250 feet MSL). In the fall, the level is drawn down, allowing abutters to make improvements to their shoreline and providing some storage for spring runoff.

4.2 Maintenance of Dike

The NHWRB is responsible for the maintenance of Gove Dike.

4.3 Maintenance of Operating Facilities

Gove Dike has no outlet facilities.

4.4 Description of Any Warning System in Effect

No written warning system was disclosed for Gove Dike.

4.5 Evaluation

The operation and maintenance procedures for Gove Dike, consisting of a weekly program of inspection, should insure that all problems encountered can be remedied within a reasonable period of time. The NHWRB should also establish a warning system to follow in event of any emergencies.



of these cottages may be susceptible to flooding. No evidence of any buildup of sedimentation is visible. (See Appendix C - Figure 5.)

e. Downstream Channel. Because the structure has no outlet, no defined downstream channel exists. The valley downstream of the dike is wooded, and drains into an unnamed tributary to the Pawtuckaway River. The valley has been cleared of trees for a distance of about 20 feet immediately downstream of the dike. (See Appendix C - Figure 6.)

### 3.2 Evaluation

The observed condition of the dike is fair. The potential problems observed during the visual inspection are listed as follows:

- (a) Two seepages at the downstream toe of the dike.
- (b) Bulge in the downstream dry masonry wall.
- (c) Brush and trees on both faces.
- (d) Crest of dike, being an unpaved road, could be subject to erosion.

SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General. The dike is a low embankment on Pawtuckaway Pond and has no spillway or outlet structures. Drown's Dam and Dolloff Dam are the controlling structures for this pond. Numerous cottages and summer homes are sited around the southeastern portion of the reservoir.

b. Dike. The dike consists of an earth embankment approximately 270 feet long, 9 feet high, and 20 feet wide at the crest. (See Appendix C - Figures 2 and 3.) The upstream side is partially faced with a nearly vertical wall of rounded boulders and the downstream face consists of a vertical dry masonry wall. Boulders comprising both walls range in size from 1 to 3 feet. The crest of the dike was approximately 3.5 feet above the pond level at the time of the inspection. The measured water depth on the upstream side varies up to 5 feet deep. The crest of the dike is an unpaved road, maintained year round (See Appendix C - Figure 4.)

Approximately 100 feet from the left abutment, a bulge was observed in the downstream dry masonry wall. The wall is bulged approximately 6 inches at a height of 4 to 5 feet above the ground level.

Numerous large boulders (4 to 5 feet in size) have apparently been dumped immediately downstream of the dike, near both ends. Two 12-inch trees have recently been cut at the west end of the dike near the downstream toe.

Two seepages were observed. One is estimated at .02 cfs (10 gpm) about 15 feet downstream of the wall near the center of the valley. The second, near the right abutment, has a barely visible flow. Discharge water from both seepages is clear. Standing water is visible approximately 20 feet downstream of the downstream face near the right abutment. Some fill has apparently been placed against the downstream face at the right abutment and filled to approximately the height of the roadway.

c. Appurtenant Structures. Not applicable

d. Reservoir Area. The reservoir slopes along the shoreline are gentle and generally covered with trees and brush. Cottages are scattered around the perimeter. Some

SECTION 2  
ENGINEERING DATA

2.1 Design

No original design data were disclosed for Gove Dike.

2.2 Construction

A report prepared by H. F. Dunham for the Lamprey River Improvement Company, dated December 5, 1918 was the earliest investigation found. Dunham's report contains a sketch of a cross section copied from a report by W. M. Oliver, C. E. to Newmarket Manufacturing Co., dated 1889. (See Appendix B.)

2.3 Operation

No engineering operational data were disclosed.

2.4 Evaluation

a. Availability. Very little engineering data were disclosed for Gove Dike. A search of the files of the NHWRB revealed only a limited amount of recorded information.

b. Adequacy. Because of the limited amount of detailed data available, the final assessments and recommendations of this investigation are based on visual inspection and hydrologic and hydraulic calculations.

c. Validity. The visual inspection is generally consistent with the 1889 sketch for the exposed portions of the dike.

- (3) Height - 11' (structural height)
- (4) Top width - approximately 20'
- (5) Side slopes - nearly vertical
- (6) Zoning - unknown
- (7) Impervious Core - unknown
- (8) Cutoff - unknown
- (9) Grout curtain - unknown
- h. Diversion and Regulating Tunnel - not applicable
- i. Spillway - none

PROJECT Gove Dike, New Hampshire

DATE May 30, 1978

PROJECT FEATURE Reservoir

NAME R. Langen

Pawtuckaway Pond

AREA EVALUATED	REMARKS
Stability of Shoreline	Good
Sedimentation	Minor
Changes in Watershed Runoff Potential	Minor
Upstream Hazards	Several homes along eastern shore. Most are at least 6' above lake.
Downstream Hazards	State Highway 156, nearest village is West Epping about 3 miles downstream.
Alert Facilities	None
Hydrometeorological Gages	None
Operational & Maintenance Regulations	None

APPENDIX B  
INSPECTION REPORTS/SKETCHES

# GOVE DIKE

## NEW HAMPSHIRE WATER CONTROL COMMISSION

### REPORT ON DAM INSPECTION

TOWN Wilmington (Nottingham) DAM NO. 184.02 STREAM Frederickson River

OWNER Longview Paper Corporation ADDRESS 145 So. Main St. Portsmouth, N.H.

In accordance with Section 20 of Chapter 133, Laws of 1937, the above dam was inspected by me on 12/21/49 accompanied by

#### NOTES ON PHYSICAL CONDITION

Abutments Good (GOOD)

Spillway None (NONE)

Gates None (NONE)

Other Embankment (EMBANKMENT - GOOD)

#### CHANGES SINCE LAST INSPECTION

FUTURE INSPECTIONS Yes (YES)

This dam (is) ~~(is not)~~ a menace because of risk of ponds  
(of area of ponds)

REMARKS Small head at dike  
(- Pawtucketway Pond)  
(184.02 - the spillway & gates also good - DROWN'S DAM)

Copy to Owner	Date

INSPECTOR

(Francis Moore)

(Additional Notes Over)

# GOVE DIKE

## NEW HAMPSHIRE WATER CONTROL COMMISSION

### REPORT ON DAM INSPECTION

TOWN Wallingford (Nottingham) DAM NO. 15402 STREAM Presidents River

OWNER Wallingford River Improvement Co. ADDRESS 111 So. Co. Rd. Wallingford, N.H.

In accordance with Section 20 of Chapter 133, Laws of 1937, the above dam was inspected by me on 12/21/49 accompanied by 12/21/49

#### NOTES ON PHYSICAL CONDITION

Abutments Good (GOOD)

Spillway None (NONE)

Gates None (NONE)

Other Embankment (EMBANKMENT - GOOD)

#### CHANGES SINCE LAST INSPECTION

FUTURE INSPECTIONS Yes (YES)

This dam (is) (~~is not~~) a menace because of rise of ponds (of area of ponds)

REMARKS Small head at dike  
(- Pawtucketway Pond)  
(154.02 - the spillway & gates also good - DROWN'S DAM)

Copy to Owner	Date

INSPECTOR

(Francis Moore)

(Additional Notes Over)



# PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

FORM 68

TOWN	NOTTINGHAM	TOWN NO.		STATE NO.	184.03
RIVER	Fartuckaway Pond (Dike)			GOVE DIKE	
STREAM					
DRAINAGE AREA	20.66 Sq. Mi.	POND AREA	934.2 Acres		
DAM TYPE	Gravity	FOUNDATION NATURE OF	Earth		
MATERIALS OF CONSTRUCTION	Boulders, Earth				
PURPOSE OF DAM	POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY				
HEIGHTS, TOP OF DAM TO BED OF STREAM	8'	TOP OF DAM TO SPILLWAY CRESTS			
SPILLWAYS, LENGTHS	None	LENGTH OF DAM	350'		
DEPTHS BELOW TOP OF DAM					
FLASHBOARDS TYPE, HEIGHT ABOVE CREST					
OPERATING HEAD			TOP OF FLASHBOARDS TO N. T. W.		
CREST TO N. T. W.					
WHEELS, NUMBER					
KINDS & H. P.					
GENERATORS, NUMBER					
KINDS & K. W.					
H. P. 90 P. C. TIME			H. P. 75 P. C. TIME		
100 P. C. EFF.			100 P. C. EFF.		
REFERENCES, CASES, PLANS, INSPECTIONS					
REMARKS					

Amprey River Improvement Co. CONTRACTOR  
c/o P. H. Burrowes, Supt. Newmarket

NO.

APPLICATION	RECEIVED	INVESTIGATED BY	DATE

IF DAM IMPROPERLY CONSTRUCTED IT would BE A MENACE TO THE PUBLIC SAFETY  
IS DAM SUBJECT TO PROVISIONS OF P. L. CHAP. 218, SECTS 13-26?

PLANS & SPECIFICATIONS	RECEIVED	CHECKED BY	DATE
APPROVED BY COMMISSION		COMMISSION CONSTRUCTION INSPECTOR	

FINAL CONSTRUCTION APPROVAL CHARGES PAID  
IS DAM SUBJECT TO PERIODIC INSPECTION? Yes

## DAM INSPECTION RECORD

DATE	INSPECTOR	REPORT	CHARGES	PAID	DATE	INSPECTOR	REPORT	CHARGES	PAID
3/15/77	C.D.C.								

NEW HAMPSHIRE WATER RESOURCES BOARD  
INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

GOVE  
DYKE

DAM

EAST RIVER Ocean NO. 1  
 RIVER Pawtuckaway Pond MILES FROM NORTH 0.4 SQ. MI. 20.66  
 TOWN Nottingham OWNER Lamprey River  
 LOCAL NAME OF DAM \_\_\_\_\_  
 BUILD \_\_\_\_\_ DESCRIPTION Gravity and earth

POND AREA-ACRES 934.2 DRAINAGE FT. 104RB POND CAPACITY-ACRE FT. 108  
 HEIGHT-TOP TO BED OF STREAM-FT. \_\_\_\_\_ MAX. MIN.  
 OVERALL LENGTH OF DAM-FT. 350 MAX FLOOD HEIGHT ABOVE CREST-FT. \_\_\_\_\_  
 PERMANENT CREST ELEV. U.S. S. S. \_\_\_\_\_ LOCAL GAGE \_\_\_\_\_  
 TAILWATER ELEV. U.S. S. S. \_\_\_\_\_ LOCAL GAGE \_\_\_\_\_  
 SPILLWAY LENGTHS-FT. NONE FREEBOARD-FT. \_\_\_\_\_  
 FLASHCARDS-TYPE, HEIGHT ABOVE CREST \_\_\_\_\_  
 WASTE GATES-NO. \_\_\_\_\_ WIDTH MAX. OPENING \_\_\_\_\_ DEPTH SILL BELOW CREST \_\_\_\_\_

REMARKS Condition Fair

into Pawtuckaway R., Lamprey R.

POWER DEVELOPMENT

UNITS	NO.	RATED HP	HEAD FEET	C.F.S. FULL GATE	KW	TAKE

USE Conservation

REMARKS \_\_\_\_\_

DATE 36

GOVE  
DIKE

PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-4582

TOWN	Nottingham	TOWN NO.	3	STATE NO.	184, 6
RIVER	Pattuckamy Pond (Dike)				
STREAM					
DRAINAGE AREA	20.60 Sq. Mi.	POND AREA	384.9 Acres		
DAM TYPE	Gravity	FOUNDATION NATURE OF	Earth		
MATERIALS OF CONSTRUCTION	Boulders, Earth				
PURPOSE OF DAM	POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTION—PUBLIC UTILITY				
HEIGHTS TOP OF DAM TO BED OF STREAM	8'	TOP OF DAM TO SPILLWAY CRESTS			
SPILLWAYS, LENGTHS	None	LENGTH OF DAM	350'		
DEPTHS BELOW TOP OF DAM					
FLASHBOARDS TYPE, HEIGHT ABOVE CREST					
OPERATING HEAD CREST TO N. T. W.	TOP OF FLASHBOARDS TO N. T. W.				
WHEELS, NUMBER KINDS & H. P.					
GENERATORS, NUMBER KINDS & H. P.					
H. P. 90 P. C. TIME 100 P. C. EFF.	H. P. 75 P. C. TIME 100 P. C. EFF.				
REFERENCES, CASES, PLANS, INSPECTIONS.					
REMARKS					

OWNER- Longrey River Improvement Company  
 CONDITION- Fair  
 VALUE- Yes. Will be subject to periodic inspection.

To the Public Service Commission:

The foregoing memorandum on the above dam is submitted covering inspection made August 6, 1935, according to notification to owner dated July 31, 1935, and bill for same is enclosed.

S. J. L., 1935  
 Copy to Owner

(Sept. 18, 1935)

Samuel J. Lord  
 Eyd. Eng.

## PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-4562

TOWN NOTTINGHAM	TOWN NO. 3	STATE NO. 101 284
RIVER STREAM Pawtucketway Pond (Dike)	GOVE DIKE	
DRAINAGE AREA 20.06 Sq. Mi.	POND AREA 954.2 Acres	
DAM TYPE Gravity	FOUNDATION Earth	
MATERIALS OF CONSTRUCTION Boulders, Earth...		
PURPOSE OF DAM POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY		
HEIGHTS, TOP OF DAM TO BED OF STREAM 8'	TOP OF DAM TO SPILLWAY CRESTS	
SPILLWAYS, LENGTHS DEPTHS BELOW TOP OF DAM None	LENGTH OF DAM 350'	
FLASHBOARDS TYPE HEIGHT ABOVE CREST		
OPERATING HEAD CREST TO N. T. W.	TOP OF FLASHBOARDS TO N. T. W.	
WHEELS, NUMBER KINDS & H. P.		
GENERATORS, NUMBER KINDS & H. P.		
H. P. 90 P. C. TIME 100 P. C. EFF.	H. P. 75 P. C. TIME 100 P. C. EFF.	
REFERENCES, CASES, PLANS, INSPECTIONS, REMARKS		

211

OWNER Lamprey River Improvement Co. c/o P. H. Burrowes, Supt. Newmarket	CONTRACTOR NO.								
RECEIVED	INVESTIGATED BY	DATE							
APPLICATION									
IF DAM IMPROPERLY CONSTRUCTED IT Would BE A MENACE TO THE PUBLIC SAFETY									
IS DAM SUBJECT TO PROVISIONS OF P. L. CHAP. 218, SECTS 15-28? Yes									
RECEIVED	CHECKED BY	DATE							
PLANS & SPECIFICATIONS									
APPROVED BY COMMISSION	COMMISSION CONSTRUCTION INSPECTOR								
FINAL CONSTRUCTION APPROVAL									
IS DAM SUBJECT TO PERIODIC INSPECTION? Yes	CHARGES	PAID							
DAM INSPECTION RECORD									
DATE	INSPECTOR	REPORT	CHARGES	PAID	DATE	INSPECTOR	REPORT	CHARGES	PAID
9/6/35	L. C. Blake	2/18/35	\$4.00	10/14/35					
Condition--Fair			35						1-

## NEW HAMPSHIRE WATER CONTROL COMMISSION

## DATA ON DAMS IN NEW HAMPSHIRE

DNR

NO. 001-07

## LOCATION

*GOVE DICE*

Town ..... (Nottingham): County ..... (Stafford)  
Stream ..... (Pawtucketaway)  
Basin-Primary ..... : Secondary .....  
Local Name .....  
Coordinates—Lat. 43° 51' - 500 ..... : Long. 71° 12' - 2300

STATE NO. 134.00

## GENERAL DATA

Drainage area: Controlled ..... Sq. Mi.: Uncontrolled ..... Sq. Mi.: Total 20.23 Sq. Mi.  
Overall length of dam 250 ft.: Date of Construction .....  
Height: Stream bed to highest elev. 2 ft.: Max. Structure 8 ft.  
Cost—Dam ..... : Reservoir .....

## DESCRIPTION

Gravity Boulders and earth Foundation earth  
Waste Gates (Gravity Boulders and earth Foundation earth)

Type .....  
Number ..... : Size ..... ft. high x ..... ft. wide  
Elevation Invert ..... : Total Area ..... sq. ft.  
Hoist .....

## Waste Gates Conduit

Number ..... : Materials .....  
Size ..... ft.: Length ..... ft.: Area ..... sq. ft.

## Embankment

Type ..... (Earth)  
Height—Max. .... ft.: Min. .... ft.  
Top—Width ..... : Elev. .... ft.  
Slopes—Upstream ..... on ..... : Downstream ..... on .....  
Length—Right of Spillway ..... : Left of Spillway .....

## Spillway

Materials of Construction .....  
Length—Total ..... ft.: Net ..... ft.  
Height of permanent section—Max. .... ft.: Min. .... ft.  
Flashboards—Type ..... : Height ..... ft.  
Elevation—Permanent Crest ..... : Top of Flashboard .....  
Flood Capacity ..... cfs.: ..... cfs/sq. mi.

## Abutments

Materials: .....  
Freeboard: Max. .... ft.: Min. .... ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER ..... (Condition fair)

## REMARKS

Subject to inspection

Tabulation By ..... Date .....  
H&B21034



PAWTUCKAWAY AND MENDUM PONDS

REPORT FROM H. F. DUNHAM

to

D. A. BELDEN, PRESIDENT

LALFREY RIVER IMPROVEMENT COMPANY

December 5, 1919

B-8

M. F. DUNHAM  
SINGER BUILDING  
140 BROADWAY, NEW YORK  
—  
APPHONE, 3167 CANTLAND

M. A. S. C. E.  
M. CLEVELAND ENGINEERING SOCIETY  
M. AMERICAN WATER WORKS ASSOCIATION

December 5, 1918.

Mr. D. A. Belden, President,  
Lamprey River Improvement Company,  
Haverhill, Mass.

Dear Sir:-

Agreeably to your request, I have made a study of conditions pertaining to the two artificial reservoirs owned by your company, known as Pawtuckaway Lake and Mendum Pond, both of which are in the towns of Nottingham and Barrington, New Hampshire. I have kept in view your desire to be informed concerning the type of construction and present condition of the various dams, spillways and controlling apparatus, and particularly as to any defects which should be remedied in the interest of public safety to life and property.

1. The reservoirs are within the drainage area tributary to the Lamprey River ten to fifteen miles westerly from Newmarket, N. H. The area tributary to each reservoir is not definitely known but has been estimated at about six square miles for the Mendum Reservoir and twenty square miles for the Pawtuckaway. More exact determination would have been made but for the fact that the U. S. Geological Survey is now plotting the notes of a quadrangle covering the reservoirs and their drainage districts. Both of the reservoirs are formed by dams built at the outlets of these small lakes and at overflow points where the higher elevation of water would cause a discharge into a depression or ravine at a distant point. There are three dams at Pawtuckaway as attached map shows, known locally as "Dollof



Dam", "Drown's Dam", and the "Gove Dam" indicated on the map respectively as Dams No. 1, 2 and 3. At Mendum's Pond there is but one dam, located at the main outlet and lying partly in the town of Barrington and partly in the town of Nottingham, hereinafter referred to as the "Mendum Dam". The dams were designed and built very nearly as they are at the present time in or between the years 1839 and 1842.

Type of Dams.

2. In a comprehensive work on "Reservoirs for Irrigation Water Power and Water Supply", published in 1900, Mr. James D. Schuyler, M. Am. Soc. C. E., devotes some seventy-five pages to rock-fill dams. His discussion in part follows:

"Rock-fill dams may be said to have originated forty or fifty years ago in the mining districts of California.....in difficult and almost inaccessible locations.....and were considered to be of a temporary nature.....They began with timber or log cribs filled with loose stone. Their next stage was an embankment of loose stone, a portion of which was laid up as a dry wall with a facing of two or more thicknesses of plank to secure water tightness. The latter type has proven so serviceable that it is still regarded as one of the most desirable classes of dam that can be built where economy is of prime importance."

Then follows an outline description of six types of rock-fill dams--including these two.

"2. Rock-fill dams with a central core of steel plates and without hand-laid facing walls."



"4. Rock-fill dams with facing of masonry built vertically backed with earth and covered on the lower side with blocks of stone laid in mortar."

Now all of these reservoir dams under consideration on the Lamprey water shed are rock-fill dams and not only were they built long before the mining days in California but they

possess permanent features, in the broad puddled clay-and-gravel cores and heavy retaining walls, superior to any of those described by Mr. Schuyler. More information about the design, the designer and the degree of originality in the construction of these dams would be very interesting. It is quite possible that the "type" had its origin in those structures. The dams have caused some anxiety at different dates and changes have been recommended and some have been made at dates that show the existence of faulty work elsewhere rather than in the dams themselves. Soon after the Mill river disaster in Massachusetts, in 1874, and again after the Johnstown flood in 1889, studies were made and the core walls in some places reinforced. In the writer's opinion there has not been a moment since the dams were built that they were unsafe--except from overtopping in some deluge too severe for the spillways to accomodate. It is of eye witness record that the water has been within an estimated "two feet" of the top of the Mendum dam and sand bags have been used on the Pawtuckaway dam No 1 on the water face wall to divert the flood to the spillway. This should not have been necessary.


Pawtuckaway - Dams No. 1, 2 and 3.

3. The dams leak a little. It may be said that all core wall dams do leak. Personal observations for more than two years, and at many different stages of water in the Pawtuckaway reservoir have been recorded, and the leaks in the main Dam (No. 1) measured in a channel constructed for that purpose. The main and waste gates do not close perfectly, but well enough for all reservoir purposes. Some water escapes at the gates--



Anderson-Nichols & Co., Inc. CONCORD NEW HAMPSHIRE	U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
GOVE DIKE PHOTO INDEX	
PAWTUCKAWAY POND	NEW HAMPSHIRE
SCALE: NOT TO SCALE DATE: JULY 1978	

APPENDIX C  
PHOTOGRAPHS



PLAN

ELEVATION

Anderson-Nichols & Co, Inc.	U.S. ARMY ENGINEER DIV. NEW ENGLAND
CONCORD	CORPS OF ENGINEERS
NEW HAMPSHIRE	WALTHAM, MASS.

**NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS**

GOVE DIKE

PAWTUCKAWAY POND	NEW HAMPSHIRE
SCALE: NOT TO SCALE	
DATE: JULY 1978	

72


72



5

5







Cross Section  
of  
MENDUM DAM  
Nottingham & Barrington N.H.  
Scale 16 to the inch.  
Copied Nov 1918 by J.H. Litchfield  
from drawings in a report by  
H.M. Oliver C.E. to the Newmarket  
Manufacturing Co. dated 1889.









Cross Section  
 of  
 GOVE DAM (No 3)  
 Nottingham N.H.  
 Scale 10' to the inch  
 Copied Nov. 1918 by J.H. Litchfield  
 from drawings in a report by  
 W.M. Oliver C.E. to the Newmarket  
 Manufacturing Co. dated 1889.



Cross Section  
of  
DROWN'S DAM (No. 2)  
Nottingham NH.  
Scale 10 to the inch  
Copied Nov. 1918. by J. H. Litchfield.  
from drawings in a report by  
H. M. Oliver C.E. to the Newmarket  
Manufacturing Co. dated 1889.



Cross Section  
 of  
 DOLLOF DAM. (No. 1)  
 Nottingham N.H.  
 Scale 10' to the inch.  
 Copied Nov. 1918. by J.H. Litchfield  
 from drawings in a report by  
 J.M. Oliver, C.E. to the Newmarket  
 Manufacturing Co. dated 1889.



Plan of  
 PAWTUCKET RESERVOIR  
 Nottingham NH  
 Reduced from a plan made by  
 John T. Haller and dated 1839  
 Reduced by J. L. Litchfield 1916  
 Scale  $\frac{1}{2}$  mile to the inch.

Mendum's.

At the Mendum reservoir there is less need to make changes. The bottom of the present spillway should be brought to a uniform level and all growth of small trees and obstacles of all descriptions, driftwood, old stumps, etc. should be removed and the entire space kept clear. One further recommendation needs attention at your convenience. The upstream wall at Mendum's is of very large rough stone, boulders for the most part, and at two or three places these have cracked under the pressure which has been concentrated at various points by the removal, through frost action in nearly a hundred years, of many of the smaller stones used in construction to level up and give added bearing surface. Last month many restorations to early conditions were made by replacement without mortar, but with much work and careful attention to strengthening the wall.

There are however three places where steel tie-rods should be introduced at a depth of about eight feet from the surface to check further outward movement at points where the overhang or bulging amount to 12 or 14 inches. The tie-rods should be not less than  $2\frac{1}{2}$  inches in diameter with upset ends and provided with washers or crabs 3 or 4 feet in diameter. The location of the rods and a section is shown in Fig. 2 on the last sheet attached to this report. The rods should be free from rust bedded and packed in fine gravel concrete in proportions 1, 2, 3. Very little need be used. The exposed parts should be painted. Then with general supervision and economic control the reservoirs should continue for a long time to give good service without causing you any anxiety or disquiet.

Yours truly,

H.F.D./R.

with stems of wood and ratchet connections. These gates are evidently of later construction and are backed up by brick work and two or three braces of wood extending to the solid ledge below the dam where the ends are bolted down. It would be simple and good construction to spring a brick arch between the vertical stone walls to hold the gate frames in place. It is within reason to think that the brick work and braces were placed as they are so that under certain pressures due to flood conditions, and perhaps with a little help, the whole construction, brick work, gates and timbers would be swept out of the way, much increasing spillway capacity. But whether that inference be correct or not, there can be no apparent harm in leaving the structure in its present condition or in replacing the wood braces when that becomes necessary.

At the Drown Dam (No.2) there are stop planks retained by timber braces more or less decayed. Renewals should be made as time may require. But all of the Pawtuckaway spillways real and imaginary, taken together, are insufficient for a drainage area of twenty (20) square miles. This can be shown conclusively by precipitation records personally witnessed where the annual totals are below those of southern New Hampshire. To provide more ample spillway capacity the Cove Dam (No.3) should be lowered or reduced in elevation about three feet over a length of two hundred and fifty feet in two sections of one hundred and twenty-five feet each as shown in Fig. 1 in the last sheet hereto attached. This will afford in addition to the other spillways a free flow for a great volume of water whenever the necessity arises. That may not be once in a century.

Their records were virtually barometer readings.)

Gate Repairs.

4. The main gates at the Mendum reservoir set in a wood from had suffered from decay making it difficult to fix upon a satisfactory estimate of leakage. Rocky creek-bed conditions below the dam interposed further difficulties. But nothing serious was observed. The gates and gate frames have just been renewed as you directed, necessary pointing in their vicinity attended to and the reservoir is now filling.

Report by Mr. W. M. Oliver, C. E.

5. In the year 1889 Mr. Oliver made a very comprehensive and valuable report upon all of these dams for the Newmarket Manufacturing Company, and this report with maps, sketches and figures is now in your possession. The maps and cross sections have been checked up carefully and found to be surprisingly accurate. This includes restored base-line measurements and distances to faces of walls. Also deep excavations were made at Mendum's to show that his cross sections were reliable. The more essential sections have been copied freely and are shown in the ink prints attached hereto with well deserved credit to Mr. Oliver in each case.

Recommendations.

6. At Pawtuckaway Dam No. 1 the main gate is at the original level of the stream and is about twenty inches by fifty inches (20" x 50"). It is raised by a wood stem with nut and screw. The stem and timber support within the gate house should be renewed at no distant date. Between this gate and the spillway there are two waste gates each three feet by three feet (3' x 3')

some through the dam itself--but all that comes through the core wall is always perfectly clear, and a recent measurement,-- November 18,-- when the surface of the water in the reservoir was two and eight tenths feet below the spillway, gives a good idea of present conditions. The total volume discharged was four and eight tenths second feet, of which it was estimated one half leaked through the gates, or reached the stream in the quarter of a mile between the dam and the measuring channel. The leakage is nearly the same in volume from each half of the dam as may be observed where it flows laterally along the buttressed lower slopes of the dam to the main gateway, the sides of which are walled up vertically from the creek bed. The volume discharged is not large considering the extent of the core wall and the pressure to which it is subjected. A recently examined earth and core wall dam, built over forty years ago in another State, could well be cited here. The dam was more than a fourth of a mile long and about thirty-five feet high. From the first there was leakage. More material was added at the foot of the water slope. Able engineers were called and accurate gaging kept for many years and recorded in annual reports. Following one of these is the comment,--

"The only variation in the discharge from the weirs appears to be due to changes in the weather."

The same statement would doubtless hold good at the Pawtuckaway and Mendum reservoirs were they accurately gaged. The early water supply for London, England, was from springs that were carefully gaged as the demand increased. Then it was observed that the discharge was greater before than it was after a rain storm.





Figure 2 - Looking at the upstream face of the dike from the west bank of the reservoir.




Figure 3 - View taken from the west abutment looking east at the downstream face.



Figure 4 - Looking west along the center of the dike from the east abutment.



Figure 5 - View looking upstream at Pawtuck-away Pond from the center of the dike.





Figure 6 - Looking at the downstream valley  
from the top of the dike.

APPENDIX D  
HYDROLOGY/HYDRAULICS



NATIONAL PROGRAM OF INSPECTION OF  
NON-FED. DAMS  
PAWTUCKAWAY POND  
GOVE DIKE  
NOTTINGHAM, NEW HAMPSHIRE  
REGIONAL VICINITY MAP  
JULY 1978  
DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASSACHUSETTS  
ANDERSON NICHOLS & CO., INC. CONCORD, NH

SCALE IN MILES  
1 1/2 0 1 2 3  
MAP BASED ON U.S.G.S. 15 MINUTE QUADRANGLE  
SHEET SUNCOOK, N.H. 1957 and  
MT. PAWTUCKAWAY, N.H. 1957

H/H  
GOVE DIKE

1018

HYDROLOGY

6/29/78  
P.O.

PAWTUCKAWAY LAKE

STEP 1: PROBABLE MAXIMUM FLOOD DETERMINATION (PMF)

RE: PRELIMINARY GUIDANCE FOR ESTIMATING  
MAXIMUM PROBABLE DISCHARGES IN PHASE I  
DAM SAFETY INVESTIGATIONS, NED - COE,  
MARCH 1978

USING FLAT & COASTAL CURVE TO DETERMINE  
PMF PEAK INFLOW

DA = 19.9 square miles (ANCO)  
DA = 20.66 " " (WRB)  
DA = 18.0± " " (Public Service Commission)  
DA = 21 " " (COE 74)  
@ DA = 20.66 square miles

$$PMF = 590 \text{ cfs/sq mile}$$

$$PMF = \frac{590 \text{ cfs}}{\text{sq mile}} \times 20.66 \text{ sq miles}$$

$$\underline{PMF = 12,200 \text{ cfs}} \quad (Q_{PI})$$

# HYDROLOGY

## FRANKLIN LAKE

218

7/7/78  
30

STEP 2: a  $Q_{p1} = PMF = 12,200 \text{ cfs}$

SURCHARGE HEIGHT TO PASS  $Q_{p1}$

RE: HYDRAULIC BACKUP FOR EACH INDIVIDUAL  
STRUCTURE; IE: RATING CURVES

TRIAL 1 - elev = 28.6

GOVE DIKE	=	0
DROWN'S DAM	=	823 cfs
DOLLOFF DAM	=	1096 cfs
		<hr/> 1919 cfs

TRIAL 2 - elev = 30.0

GOVE DIKE	=	617 cfs
DROWN'S DAM	=	1636
DOLLOFF DAM	=	2243
		<hr/> 4496 cfs

TRIAL 3 - elev = 31.0

GOVE DIKE	=	1455
DROWN'S DAM	=	2787
DOLLOFF DAM	=	3842
		<hr/> 8084 cfs

TRIAL 4 - elev @ 32.0

GOVE DIKE	=	3382
DROWN'S DAM	=	5062
DOLLOFF DAM	=	6427
		<hr/> 14871 cfs

318

7/7/78

Bo

HYDROLOGY  
DAWPUCKAWAY LAKE

FROM THE ABOVE TRIALS A RATING CURVE FOR THE  
LAKE CAN BE DRAWN. READING THE ELEVATION  
AT THE PMF

@ PMF = 12,200 cfs  
elev = 31.65

GOVE DIKE = 2596 cfs  
DOLLOFF DAM = 5430  
DROWN'S DAM = 4127  

---

12153 cfs

SINCE THIS IS LESS THAN PMF  
ROUND ELEVATION UP TO 31.7

∴ SURCHARGE HEIGHT =  $31.7 - 25.0 = 6.7'$

(ABOVE SPILLWAY)

## VOLUME OF SURCHARGE HEIGHT

INVENTORY -	DAM	MAX	NORMAL
	Dolloff Dam	14700	11500
	Gove Dike	14700	11500
	Drown's Dam	14700	11500


normal lake level = 903A @ elev 25.0 (SPILLWAY)  
elevation 260 (QUAD) = 1482A @ elev 25+10 = 35.0

STOR @ 31.7 = 13700 AF  
@ 25.0 = 11500 AF } SEE STOR-ELEV

∴ STOR, (SURCHARGE) = 2200 AF




498



D-5

35  
33  
31  
29  
27  
25



NOTE: 25.0 = SPILLWAY  
@ DOLLOFF DAM

16000 17000 18000

ANDERSON-NICHOLS

VERNON BOSTON CONCORD

PAWUCKAWAY LK  
STORAGE ELEVATION

11000 12000 13000 14000 15000  
STORAGE IN AF

DATE 7/10/78 SCALE: AS SHOWN JOB NO. 31411-13 SHEET NO. 151

5980

HYDROLOGY  
PAWTUCKAWAY LAKE

6-7-8

7/10/78  
(3)

$$2200 \text{ AF} \times \frac{1}{20.66 \text{ mi}^2} \times \frac{\text{mi}^2}{640 \text{ A}} = 0.17 \text{ A}$$

0.17 A = 2 inches of RUNOFF OVER BASIN

C. DETERMINATION OF  $\Phi_{P2}$

$$\Phi_{P2} = \Phi_{P1} \times \left(1 - \frac{\text{STOR}_1}{19}\right)$$

$$= 12200 \text{ cfs} \times \left(1 - \frac{2}{19}\right)$$

$$= 12200 \text{ cfs} \times 0.895$$

$$= \underline{\underline{10916 \text{ cfs}}}$$

718

DROLOGY  
HUCKAWAY LAKE

7/10/78  
Bo

EP 3a) SURCHARGE HEIGHT TO PIES  $Q_{P2}$

$$Q_{P2} = 10916 \text{ cfs}$$

FROM RATING CURVE : elev = 31.46

$$\text{SURCHARGE HEIGHT} = 31.46 - 25.0 = \underline{\underline{6.46'}}$$

FROM STORAGE-ELEVATION CURVE

$$\text{STOR @ 31.46} = 13500 \text{ AF}$$

$$\text{STOR @ 25.0} = 11500 \text{ AF}$$

$$\therefore \text{VOL OF SURCHARGE} = 2000 \text{ AF}$$

$$2000 \text{ AF} \times \frac{1}{20.66 \text{ mi}^2} \times \frac{\text{mi}^2}{640 \text{ A}} = 0.151 \text{ ft}$$

$$0.151 \text{ ft} = \underline{\underline{1.82 \text{ inches over BASIN}}}$$

b. AVERAGE SURCHARGE & PEAK OUTFLOW ( $Q_{P3}$ )

$$\left. \begin{array}{l} \text{STOR}_1 = 2.0'' \\ \text{STOR}_2 = 1.8'' \end{array} \right\} \text{AVE} = 1.9''$$

$$1.9'' \times 20.66 \text{ mi}^2 \times \frac{1 \text{ ft}}{12''} \times \frac{640 \text{ A}}{1 \text{ mi}^2} = 2094 \text{ AF}$$

$$2094 \text{ AF} + 11500 \text{ AF} = 13594 \text{ AF}$$

HYDROLOGY  
PAWTUCKAWAY LAKE

8 of 8

7/10/78  
30

FROM SDR-ELEV CURVE:

@ 13594 AF  $\rightarrow$  elev = 31.5

FROM RATING CURVE:

31.5 = 11200 cfs =  $Q_{P3}$

CHECK of  $\frac{1}{2}$  PEAK OUTFLOW

$\frac{1}{2}$  PEAK OUTFLOW = 5600 cfs

FROM RATING CURVE

5600 cfs  $\rightarrow$  30.41 ft

103

7/6/78  
Bo  
3141-12Gove Dike  
Rating Curve Camps

$$Q = CLH^{3/2}$$

$$C = 2.7$$

25.0 = SPILLWAY @  
DOLLOFF DAM

@ 28.6  $Q = 0$

@ 28.8  $H = 0.2'$   
 $L_1 = 78' \Rightarrow L = 39'$

$$Q = CLH^{3/2}$$

$$= 2.7(39)(0.2)^{3/2}$$

$$= 9.4 \text{ cfs}$$

9.4 cfs

@ 28.9  $H = 0.3'$  OVER WEIR

①  $H = 0.3'$   
 $L = 130' \Rightarrow L = 65'$   
 $Q = CLH^{3/2}$   
 $= 2.7(65)(0.3)^{3/2} = 28.8 \text{ cfs}$

②  $H = 0.1'$   
 $L = 56' \Rightarrow L = 28'$   
 $Q = CLH^{3/2}$   
 $= 2.7(28)(0.1)^{3/2} = 2.4 \text{ cfs}$   
 $\frac{2.4 \text{ cfs}}{31.2 \text{ cfs}}$

31.2 cfs

@ 29.0  $H = 0.4'$  OVER WEIR

①  $H = 0.1'$   
 $L = 245'$   
 $Q = CLH^{3/2}$   
 $= 2.7(245)(0.1)^{3/2}$   
 $= 20.9 \text{ cfs}$

ADD TO THE PREVIOUS TOTAL  $\Rightarrow 20.9 + 31.2 = 52.1 \text{ cfs}$

5. @ 29.3  $H = 0.7'$  OVER WEIR

$$\begin{aligned} \textcircled{1} \quad H &= 0.4' \\ L &= 275' \\ Q &= CLH^{3/2} \\ &= (2.7)(275)(0.4)^{3/2} \\ &= 187.8 \text{ cfs} \end{aligned}$$

$$\text{ADD TO THIS TRIAL 2} \quad 187.8 + 31.2 = 219.0$$

2. @ 29.6  $H = 1.0'$  OVER WEIR

$$\begin{aligned} \textcircled{1} \quad H &= 0.3' \\ L &= 327' \\ Q &= CLH^{3/2} \\ &= 2.7(327)(0.3)^{3/2} \\ &= 145.1 \text{ cfs} \end{aligned}$$

$$\text{ADD TO THIS THE PREVIOUS TRIAL} \quad 145.1 + 219.0 \Rightarrow 364.1$$

1. @ 30.0  $H = 1.4'$  OVER WEIR

$$\begin{aligned} \textcircled{1} \quad H &= 0.4' \\ L &= 370' \\ Q &= CLH^{3/2} \\ &= 2.7(370)(0.4)^{3/2} \\ &= 252.7 \end{aligned}$$

$$\text{ADD TO THIS THE PREVIOUS TRIAL} \quad 252.7 + 364.1 = 616.8$$

3. @ 30.4  $H = 1.8'$  OVER WEIR

$$Q = (2.7)(417)(0.4)^{3/2} + 616.8 = 901.6 \text{ cfs}$$

3073

@ 31.0 H = 2.4' OVER WEIR

$$Q = (2.7)(441)(0.6)^{3/2} + 901.6 = \underline{1455 \text{ cfs}}$$

1. @ 32.0 H = 3.4' OVER WEIR

$$Q = (2.7)(454)(1.6)^{3/2} + 901.6 = \underline{3382.4 \text{ cfs}}$$


@ 31.65 H = 3.05' OVER WEIR

$$Q = (2.7)(449)(1.25)^{3/2} + 901.6 = \underline{2596 \text{ cfs}}$$




ELEVATION IN FEET

D-13



DISCHARGE IN CFS



600 700 800

ANDERSON-NICHOLS

VERNON	BOSTON	CONCORD
GOVE DIKE		
RATING CURVE - PART 1		
DATE 7/5/78	SCALE AS SHOWN	JOB NO. 3141-12
		SHEET NO. 101

PAWBUCKAWAY LAKE  
GOVE DIKE  
30 8/16/78  
DOWNSTREAM HAZARD

ASSUME FAILURE AT FULL POOL CONDITIONS.  
FULL POOL IS DEFINED AS MAXIMUM POOL

GOVE DIKE

MAX POOL = 252.7 MSL

PEAK FAILURE OUTFLOW FROM BREACH:

$$Q_B = (8/27) W_b \sqrt{g} y^{3/2}$$

$W_b$  = BREACH WIDTH

$g$  = 32.2 ft/sec<sup>2</sup>

$y$  = POOL LEVEL → RIVER BED

ASSUMING OTHER STRUCTURES HOLD  
BREACH WIDTH = 50'

REACH 1


$$Q_B = \left(\frac{8}{27}\right)(50)(\sqrt{32.2})(252.7 - 245.0)^{3/2}$$

$$= 1800 \text{ cfs}$$

NO OTHER INFLOW INTO REACH OTHER  
THAN THAT FROM BREACH

FROM D/S HAZARD REACH 1 RATING CURVE:  
← DIKE TO RTE 156

STAGE @ 1800 cfs = 2.5 FEET



REACH 1 LENGTH = 2000' ±

VOLUME WITHIN REACH =  $V_1$

$$V_1 = 2000 \times 590 = 27 \text{ AF}$$

STORAGE @ MAX. POOL = 11700 AF = S

$$V_1 < \frac{1}{2} S \quad \therefore \text{REACH OK}$$

$$\begin{aligned} Q_2 &= Q_B (1 - V_1/S) = 1800 (1 - 27/11700) \\ &= 1800 \text{ cfs} \quad (\text{vol negligible}) \end{aligned}$$

@  $Q = 1800 \text{ cfs}$

STAGE = 2.5 FEET

STORAGE WITHIN REACH = 27 AF

REACH 2

INFLOW INTO REACH = 1800 cfs

FROM D/S HAZARD REACH 2 RATING CURVE  
(FOR BOTH DOLLOFF & GOVE DIKE):  
FROM RTE 156 TO EPI

STAGE @ 1800 cfs = 6.6 FEET

REACH 2 LENGTH = 14000'

VOLUME WITHIN REACH =  $V_2$

$$V_2 = 14000 \times 750 = 240 \text{ AF}$$

SINCE  $V_2 < \frac{1}{2} S$  D-17 REACH OK ✓

$$Q_2 = Q_1 (1 - V_2/S) = 1800 (1 - 240/11700) \\ = 1765 \text{ cfs}$$

@ 1765 cfs; STAGE = 6.6 FEET

SINCE THIS WOULD RESULT IN THE SAME  
VOLUME WITHIN REACH


$$Q_{\text{FINAL}} = (1800 + 1765) / 2 = 1780 \text{ cfs}$$

@  $Q = 1780 \text{ cfs}$

STAGE = 6.6 FEET

SDR = 240 AF

WAVE INTO EPPING



APPENDIX E  
INFORMATION AS  
CONTAINED IN THE NATIONAL  
INVENTORY OF DAMS



**END**

**FILMED**

**8-85**

**DTIC**